BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2019-20/OW/WORK_INDENT38009

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/15/2019-20, Date: 01.10.2019

Name of Work: Desilting of drains at Kodigehalli and surrounding areas in ward no. 08 Kodigehalli

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of KARTHIKYADAV C P ( )	
				In Figures	In Words
1	1077.3	Removing and refixing stone slabs of drains and pointing in CM 1:3 cost of all materials, labour, HOM of machineries, curing etc., complete with all leads and lifts as per specifications.	sqm	94.61	Rupees Ninety Four and Sixty One Paise Only
2	266	Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2m and an average lift upto 1.5m excavated surface levelled and sides neatl;y dressed, the disposed earth to be levelled neatlyu after breaking of clods complete as per specifications.	cum	100.0	Rupees One Hundred Only
3	119.7	Providing and laying in position reinforced cement concrete M20 mix with stone aggregates 20mm and downsize for slab (including steel reinforcement) including centering and shuttering, maching mixed, concrete laid in layers not exceeding 15cm thick well compacted cost of all materials, labour, HOM of machineries, curing complete as per specifications.	Sqm	1785.0	Rupees One Thousand Seven Hundred Eighty Five Only
4	226.1	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading with all leads and lifts as directed by the Engineer in charge of the work.	cum	74.0	Rupees Seventy Four Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

23/02